

AMESBURY HERITAGE PARK
BROWNFIELD SOILS REMOVAL AND REMEDIATION



**CONTRACT DOCUMENTS AND TECHNICAL SPECIFICATIONS
FOR
AMESBURY HERITAGE PARK
BROWNFIELD SOILS REMOVAL AND REMIDATION
AMESBURY, MA
ADDENDUM #2
NOVEMEBR 1, 2013**

NOTICE TO ALL BIDDERS please be advised of the following changes:

A. Clarifications:

- 1) **Question:** Spec Section 01010 states that 2,600 SF of Asphalt is to be excavated and disposed of. Bid Item 13 says 2,600 tons. Please clarify which is to be assumed?

Answer: **Section 00300 – BID FORM - Item #13;** - Asphalt quantity to be excavated and disposed should be 2,600 SF not 2,600 TONS as indicated. Please provide indication on the submitted Bid Forms to acknowledge the Unit Change.

- 2) **Question:** Spec Section 02400, Dewatering, Control, and Diversion of Water references Elevation 73 a normal elevation that the pond is operated at. I can't find any reference to elevations on the plans provided to determine whether or not the contractor will be hitting water when performing the excavation (i.e. groundwater elevation). Please clarify.

Answer: **Section 02400 – DEWATERING, CONTROL, AND DIVERSION OF WATER;** Please disregard the reference to Elevation 73 as a normal elevation that the pond is operated at. This information does not pertain to this Project Document.

- 3) **Question:** Please confirm that Sheets 1 of 2 and 2 of 2 are the only plans applicable to this project?

Answer: **Yes,** Sheets 1 of 2 and 2 of 2 are the only Plans for the Project Documents.

- 4) **Question:** Please confirm that the "Excavation Cross Section Detail" shown on Sheet 1 of 2 and Sheet 2 of 2 is applicable to all excavation work (i.e. 18" cut).

Answer: **Section 00100 – INFORMATION FOR BIDDERS –** Project Identification Paragraph E indicates approximated range in depths of excavation work for the project.

- 5) **Question:** We are required to install a 3" Binder Course Asphalt Temporary Riverwalk. There is no specification on the asphalt. Please provide.

Answer: **MassDOT Standard Specifications** for Binder Course Asphalt Pavement shall be referenced for the Temporary Riverwalk Asphalt.

AMESBURY HERITAGE PARK
BROWNFIELD SOILS REMOVAL AND REMEDIATION

6) **Question:** Bid Form Items 10 and 11 have the same quantity (5,082 tons) of soil to be disposed of off-site. Are we expected to dispose of approximately $5,082 + 5,082 = 10,164$ tons for the project or is the total expected to be 5,082 tons for all material? If 5,082 tons is the expected quantity to be disposed of off-site, please consider changing the bid form.

Answer: **Section 00300 – BID FORM - Items #10 and #11;** - Bid quantities for both these Items should be **2,541 TONS** not 5,082 Tons as indicated. Please provide indication on the submitted Bid Forms to acknowledge the Bid Quantity Change.

7) **Question:** When is the work anticipated to be performed?

Answer: **Section 00100 – 1.12 NOTICE TO PROCEED AND 1.13 TIME SCHEDULE FOR COMPLETION OF WORK;** provides clarification for the duration of the Project from the Date of Notice to Proceed. Project is anticipated to begin shortly thereafter the Bid Opening Date and Contract Award.

8) **Question:** What / where does the Engineer/Owner think that a cofferdam will need to be installed to perform this work per specification 02400?

Answer: **Section 02400 – DEWATERING, CONTROL, AND DIVERSION OF WATER;** Please disregard the reference to a cofferdam will need to be installed to perform this work. This information does not pertain to this Project Document.

Respondents are requested to confirm receipt of this addendum.

Please send signed confirmation via
EMAIL: joni@amesburyma.gov
or
FAX: 978 388-6727

~~~~~

**ACKNOWLEDGMENT**

The undersigned of \_\_\_\_\_ indicates receipt of  
(COMPANY NAME)

ADDENDUM 2 issued November 1, 2013

\_\_\_\_\_  
SIGNED

\_\_\_\_\_  
DATE

Office of Community & Economic Development  
Addendum 2 (11/1/2013) - Amesbury Heritage Park - Brownfield Soils Removal and Remediation